

Noble Resolve

General

Rig Type:	Jackup
Rig Design:	Gusto MSC CJ50 X100 MC
Builder:	Keppel Fels Shipyard Singapore
Year Built / Upgraded:	2009
Classification:	ABS A1 Self Elevating Drilling Unit IMO, MODU, SOLAS and Marpol
Flag:	Marshall Islands
MODU Code:	

Ratings & Dimensions

Water Depth:	350 ft
Drilling Depth:	30,000 ft
Length:	230 ft
Breadth:	223 ft
Depth:	31,2 ft
Leg Length:	480 ft
Leg Spacing:	164 ft / 164 ft
Draft (Operating/ Transit):	18 ft transit
Cantilever Envelope:	70 ft x 45 ft (x-y skidding system)
Variable Deck Load:	9,900 kips
Hook Load:	1,500 kips
Setback Capacity:	1,320 kips
Quarters Capacity:	120

Capacities

Fuel:	3,396 bbls
Drill Water:	5,500 bbls
Liquid Mud:	6,290 bbls
Brine Storage:	3,145 bbls
Base Oil Storage:	1,572 bbls
Bulk Storage:	17,600 cu ft
Sack Storage:	5,000 sacks



Equipment

Derrick:	NOV capacity 1,500 kips
Racking Capacity:	
Drawworks:	Wirth GH 1,5MIbs; 3,500 continuous / 4,500 HP intermittent
Top Drive:	MH DDM-750 -AC; 60,400 ft-lbs continuous torque
Rotary:	Wirth RST; 49-1/2 in
Iron Roughneck:	1 ea Aker MH Iron roughneck MH 1899 w/ mud bucket 1 ea Aker MH Torquemaster
BOP:	Main: Hydril 18 3/4" 15,000psi
LMRP:	N/A
Control System:	TBD
Pipe Handling System:	MH Eagle light system, X2 dual pipe racker system, pipe catwalk shuttle and pipe handling knuckleboom crane
Solids Control /System:	(4) Cubility - mud cube
Diverter:	Vetco Grey KFDJ 500 (min 36 1/4" ID")
Cranes:	(2) Favelle Favco (capacity 176,000 lbs at G5ft) (1) KBC MH Pipehandler crane 26,000lbs
Mud Pumps:	(3) Wirth 14"-2200Hp Triplex 7,500psi
Engines:	(4) 2,340kW ea
Jacking System:	OTD 1000FV80

These specifications are intended for informational purposes only. Noble makes no warranties about the accuracy or completeness of any information contained herein.

