



VALARIS DS-10



SAMSUNG GF12000 Drillship • Year in Service: 2017

DESIGN

Design

Samsung 78k Drillship

Shipyard Delivery

2017

Shipyard

Samsung Heavy Industries, South Korea

Classification Agency

ABS

Flag State

Marshall Islands

Drilling Systems

NOV

Subsea Systems

NOV

PROPULSION & POWER

DP Class

DPS-3

Emergency Power

1,700 kW

Main Engines

(6) Wartsila 7,6800 kW

Thrusters

(6) Rolls-Royce azimuthing type,
5.5 MW each

DRILLING EQUIPMENT

Derrick

Simultaneous: 1,750 t

Main: 1,250 t

Aux: 1,000 t

Rotary Table

Main: 75 1/2", 1,250 st

Aux: 60 1/2", 1,000 st

Top Drives

Main: NOV AC 1,250 t

Aux: NOV AC 1,250 t

Motion Compensator

Incorporated in with Active Heave Drawworks

Drawworks

Main: NOV 1,250 st, 9,000 hp AHD

Aux: NOV 1,000 st, 6,900 hp AHD

Iron Roughnecks

(2) 2 3/8" - 20"

GENERAL SPECIFICATIONS

Length Overall

754.6ft

Breadth

124.7ft

Depth at Side

60.7ft

Draft (Max. Operating)

36.1ft

Displacement

77,000 MT

Rated Max. Water Depth

12,000ft

Moonpool, Opening at Baseline

42ft x 81.37ft

Max. Drilling Depth

40,000ft

Variable Deck Load

22,000 MT

Heliport

EH101 Helicopters

Accommodations

200 persons

Changes / modifications to the above listed equipment could occur.

Maximum Water Depth denotes the designed rating, pending site specific assessment.

Should you have specific questions, please contact the Marketing Department at: marketing@valaris.com



VALARIS DS-10



■ CAPACITIES

Diesel Fuel Oil

42,020 bbl

Drillwater

16,800 bbl

Liquid Mud

16,279 bbl

Bulk Storage

Barite: 670 m³

Cement: 670 m³

Fresh Water

7,540 bbl

Base Oil

7,540 bbl

Brine/Completion Fluid

7,540 bbl

■ WELL CONTROL & MUD SYSTEM

Mud Pumps

(4) 14-P-220, 2,200 hp

Mud System Pressure

7,500 psi

Shale Shakers

(6) Brandt VSM-300

BOP Stack #1

(2) 10,000 psi Annulars,

(7) ram 15,000 psi BOP

BOP Stack #2

(2) 10,000 psi Annulars,

(7) ram 15,000 psi BOP

Control System

NOV 6th gen multiplex

Diverter

74" 500 psi

Choke Manifold

15,000 psi upstream, 10,000 psi downstream, H₂S rated, (2) auto, (2) manual, (1) by-pass choke design

■ RISER SYSTEMS

Riser

GE Vetco MR-6H SE 3.5m lbs,

21 ¼" OD, 75 ft joints

Riser Tensioning

(16) 225,000 lbs each,

3,600,000 lbs total

Riser Length

10,050 ft

Riser Handling

(2) below deck riser gantry cranes

(1) riser catwalk machine with

tailing arm

(2) riser elevation system from bay

to deck

(1) riser bridge crane for joint

transfer from elevation system to

catwalk

■ HANDLING SYSTEMS

Cranes

(2) 85 MT KBC, (1) 165mt AHC,

(1) 85 MT pedestal crane

Tubular Handling

(1) NOV Piperack handler,

(2) Hydrackers 3 ½" to 20"

BOP Handling

(1) 480 MT Hydralift Overhead Crane

with (1) BOP Carrier rated 540 MT

Xmas Tree Handling

Xmas Tree deck setback, (1) Xmas

Tree overhead crane 150 MT

Additional

(1) Xmas tree trolley with 350 MT for

casing and guid base hang-off load

■ LIFESAVING SYSTEMS

Lifeboats

(4) 60 persons

(2) 80 persons

Rescue Boat

(1) davit launched

REVISED 3/2025

Changes / modifications to the above listed equipment could occur.

Maximum Water Depth denotes the designed rating, pending site specific assessment.

Should you have specific questions, please contact the Marketing Department at: marketing@valaris.com